EXTRA ITEM RATE LIST

e of Work: Improvements to Roads and Drains at Thindlu and Kodigehalli Surrounding Areas in Ward No.09 igehalli.

ne of Agency: Sri Subbareddy K.V, # 106/B, Aswathnargara, RMV 2nd Stage, Bangalore - 94.

mated Cost: 1,00,00,000.00

der Amount : Rs. 91,69,441.94

k Order No. BBMP/EE/BTP/WO/56/2021-22 Dated: 18-03-2022.

tem No.	Description of Work	Unit	Qty	Rate	Amount	Whether the items are alternative to items in tender schedule or whether being an additional item	Wheather the extra items s included in the sanctioned Estimate	How the expenditure due to the extra item is proposed to be met out	Whether the item isincluded in the S.R (Referabce if SR to be given . If not Data Should accompany the EIRL	Remarks
E1	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead By Mechanical Means - Cement Concrete Grade M-15 & M-20	Cum	62.24	1015.52	63205.96	Additional Item	No	By over all savings in the work	2016-17 PWD SR Rates	
E2	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:5:10 Using 40 mm nominal size graded crushed coarse aggregates	Cum	62.24	5735.79	356995.57	Additional Item	No	By over all savings in the work	2016-17 PWD SR Rates	

tem No.	Description of Work	Unit	Qty	Rate	Amount	Whether the items are alternative to items in tender schedule or whether being an additional item	Wheather the extra items s included in the sanctioned Estimate	How the expenditure due to the extra item is proposed to be met out	Whether the item isincluded in the S.R (Referabce if SR to be given . If not Data Should accompany the EIRL	Remarks
E3	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14-days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete. as per the directions of the Engineer-in-charge of the work	Cum	62.24	7880.94	490509.71	Additional Item	No	By over all savings in the work	2016-17 PWD SR Rates	
	Total				**910711.24**					

Percentage Excess $\frac{\textbf{910711.24}}{\textbf{9169340.63}} \times 100 =$ 9.93%

Approved Tender Amount

Assistant Engineer
New Ward No. 11

Assistant Executive Engineer
Kodigehalli Sub Division
BBMP, Bangalore - 97

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ